



STEINSTEYPA

STEYPA ER C25/30 MED A.M.K. 300 Kg SEMENT l m³.

LOFTINNIHALD STEYPU V/S-TALA (UMHVERFISFLOKKUR 2b) : 6-8 %

SÍGMÁL STEYPU (S2) : < 0.55

MESTA STEINASTÆRD : 50 - 90 mm

TITRA SKAL ALLA STEYPU. : 32 mm

STEYPUHULA Á JÄRNUM

GILDIN EIGA VID UM VENJULEGAR ADSTÆÐUR, EF ANNAD ER EKKI SYNT Á TEIKNINGUM. ÞAR SEM TÆRINGARHÆTTA ER MIKIL GILDA ADRAR REGLUR UM STEYPUHULU JÄRNA.

INNANHÜSS	PLÖTUR	VEGGIR	BITAR	SÜLUR
15	20	20	20	20
UTANHÜSS	25	25	25	25
SÖKKLAR	35	35	35	35
STEYPT AD JÖRD	50	50	50	50

UM BITA OG SÜLUR GILDIR EINNIG: C1 ≥ 1.5xd

STEYPUSTYRKARSTÁL

STÁLGÆDI: K - KAMBSTÁL fyk = 500 MPa

BEYGING STÁLS d = ALLIR SVERLEIKAR

SKEYTING BENDISTÁLS ER SAMKVÆMT EFTIRFARANDI: D = 5 x d

ÞVERMÁL STÁLS, d l mm	10	12	16
SKEYTILENGD l mm	500	600	800

LÁRÉTT JÄRN SEM KOMA Í HORN EDA ÞVERVEGG SKAL BEYGJA SKEYTILENGD FYRIR HORN.

BENDING Í SÖKKULVEGGI

2 K12 EFT OG NEDST

K10 c/c 250 LÓDRÉTT

K10 c/c 300 LÁRÉTT.

MÁL ERU l mm NEMA ANNARS SÉ GETID.

ÚTGÁFUFERLI

ÚTGÁFA NR.	ÚTGEFID DAGS.	ÚTGEFID AF	SKÝRINGAR
U2	11.10.2006	Þ.S.	GÖLFKÓTI HÆKKADUR ÚR 26.70 Í 27.00

VERKFRÆÐISTOFA ÁRBORGAR ehf

AUSTURVEGI 69 800 SELFOSSI

SÍMI 480 4900 FAX 482 3851

www.verkarborg.is verkarborg@verkarborg.is

AUSTURVEGI 69 800 SELFOSSI

SÍMI 482 3850 FAX 482 3851

NETFANG sghus@sghus.is

VEFANG www.sghus.is

GLITVELLIR 33

BURDARVIRKI: MKV:

SNID Í SÖKKUL MKV: 1:20

SKÝRINGAR OG GRUNDUN MKV: 1:50

HANNAÐ: TELLERT TÓMASSON TEIKNAD: LAURA APARISI

VERKNÖMUR: 6038 SKÝRARNAFN: 6038-bv.dwg

DAGSETNING: 12.04.2006 SAMÞYKKT: [Signature] TEIKNING NÖMUR: 202

201170-3979