



SKÝRINGAR

STEYPA S-250, SEMENTINNIHALD = 300kg/M
 STEYPUHULA Í ÖTVEGGJUM = 30mm
 STEYPUHULA Í PLÖTU = 20mm
 BENDISTÁL Ka410

BENDING VEGGJA
 ÖTVEGGJIR TVÖFÖLD GRIND K10 c/c 150#
 Milliveggir tvöföld grind
 K10 c/c 150#
 Milliveggir einföld grind
 K12 c/c 150#

Br.	Dags.	Eðli breytinga	Sign
NORÐURBAKKI 11 OG 13 HAFNARFIRÐI			
BENDING VEGGJA KJALLARA BENDING PLÖTU YFIR KJALLARA			
MKV. 1:50 1:20			
SEPT. 2006			
2513			
1-13			
SIG. ÞORLEIFSS. KÖ. 24 148-3009			
G.H.			
k10 c/c 200			
k10 c/c 200			