



16 UPPSTIG  
 $16 * 171,9\text{mm(UPPSTIG)} = 2750\text{mm}$   
 FRAMSTIG 270 mm  
 UPPSTIG 171,87 mm  
 INNSKOT 40mm  
 $2 * \text{UPPSTIG} + 1 \text{ FRAMSTIG}$   
 $343,75 + 270,0 = 613,5\text{mm}$

ATH: VERKTAKI YFIRFARI ÖLL MÁL AÐUR EN FRAMKVÆMDIR HEFJAST. AÐSAMRÆMI Í TEIKNINGUM TILKYNNIST TEIKNISTOFUNNI ÖLL VAFÁATRÍÐI SKAL BERA UNDIR TEIKNISTOFUNA.

<b>es</b>		TEIKNISTOFAN SUÐURLANDSBRÁUT 48	
		S: 588-7344 FAX: 588-7343	
		NETFANG: kastor@simnet.is	
KLUKKUVELLIR 40-50			
INNISTIGI		kv	1:10
LIÑIÐ	KJARTAN	TÍÐIÐ	KJARTAN
TÍÐNÚMÉR	0105-07	SÍÐANAFN	KLUKKUVELLIR.dwg
ÞEGING		TÍÐNÚMÉR	
07.02.2008			A-08