



STEINSTEYPA

STEYPA ER C25/30 MED A.M.K. 300 Kg CEMENT í m<sup>3</sup>.

LOFTINNIHALD STEYPU V/S-TALA (UMHVERFISFLOKKUR 2b) : < 0.55

SIGMÁL STEYPU (S2) : 50 - 90 mm

MESTA STEINASTÆRD : 32 mm

TITRA SKAL ALLA STEYPU.

STEYPUHULA Á JÄRNUM

GILDIN EIGA VID UM VENJULEGAR ADSTÆÐUR, EF ANNAD ER EKKI SÝNT Á TEIKNINGUM. ÞAR SEM TÆRINGARHÆTTA ER MIKIL GILDA ADRAR REGLUR UM STEYPUHULU JÄRNA.

INNANHÜSS	PLÖTUR	VEGGIR	BITAR	SÚLUR
15	20	20	20	20
25	25	25	25	25
35	35	35	35	35
50	50	50	50	50

UM BITA OG SÚLUR GILDIR EINNIG: C1 ≥ 1.5xd

STEYPUSTYRKARSTÁL

STÁLGÆDI: K - KAMBSTÁL fyk = 500 Mpa

BEYGING STÁLS d = ALLIR SVERLEIKAR

SKEYTING BENDISTÁLS ER SAMKVEMT EFTIRFARANDI: D = 5 x d

ÞVERMÁL STÁLS, d í mm	10	12	16
SKEYTILENGD í mm	500	600	800

LÁRÉTT JÄRN SEM KOMA Í HORN EDA ÞVERVEGG SKAL BEYGJA SKEYTILENGD FYRIR HORN.

BENDING Í SÖKKULVEGGI

2 K12 EFT OG NEDST K10 c/c 250 LÖDRÉTT K10 c/c 300 LÁRÉTT.

MÁL ERU í mm NEMA ANNARS SE. SETID: 2006

VERKFRÆÐISTOFA ÁRÞORGAR ehf. AUSTURVEGI 69 800 SELFOSSI SÍMI 480 4900 FAX 482 3851 www.verkarborg.is verkarborg@verkarborg.is

AUSTURVEGI 69 800 SELFOSSI SÍMI 482 3850 FAX 482 3851 NETFANG sghus@sghus.is VEIÞFANG www.sghus.is

**SKVISTAVELLIR 19**

BURDARVIRKI: MKV:

SNID Í SÖKKUL MKV: 1:20

SKÝRINGAR OG GRUNDUN MKV: 1:50

HANNAÐ: T. ELLERT TÓMÁSSON TEIKNAD: LAURA APARISI

VERKNÚMÉR: 6058 SKRÁRNAMN: 6058-bv.dwg

DAGSETNING: 13.09.2006 SAMÞYKKT: T. Ellert TEIKNING NÚMÉR: 202

201170-3979