



SKÝRINGAR:
 UNDIRSTÖÐUR STANDA Á KLÖPP. ALAG VERÐUR MINNA EN 80 TON/M²
 STEYFUGÆÐI S-160 Í UNDIRSTÖÐUVEGGI OG
 GÓLFPLÖPU, SEM STEYPIST MINNST 12 CM.
 STEYFUSTRYKTARSTÁL KS 40 MERKT -K-
 ST 37 MERKT -Ø-
 EFST OG NEDST Í UNDIRSTÖÐUVEGGI KOMA
 2 K 10, VINKLAR K 10 L-80+80 FYRIR HORN

21. sept. 1979

STEINGRÍMUR TH. ÞORLEIFSSON, MTFI		
TEIKNISTOFA - ARMULA 5 - SIMI 3-22-44		
VERK	FJÓLUHVAMMUR NR. 9 - HAFNARFJÖRÐ	
MÁL	1:50-1:20	JÄRNBENT STEINSTEYPA
DAGS	SEPT. 1979	-UNDIRSTÖÐUR
BLAD	1	-GRUNNMYND
BREYTT		-SNID
<i>S. Leifsson</i>		