



**Skýringar** Útveggjasteypa skv gr 7242 a Byggingareglugerð Steypa S250 en S200 í sokklum og botnplötu Stál KS40 en lykjur KS40S Göt í sokkla skv fræmstístaekningu Kringum all op 2K12 sem na 60cm uffyrn brun ops Undirstöður a klopp/mohelnu með leyfilegt alag 300kn/m<sup>2</sup> Mesta alag a undirstöður 430 kn/m<sup>2</sup>

Breytingar			Lækjarberg 19	
Nr	Dags	Nafn	BJARNI ARNASON	Tæknifræðingur MTFÍ S 642260
1	16/10 90	Bjarni	Smidjuvegi 11	H BA JT BA JS M 150
			Grunnmynd sokkla	Nr 1B Dags 22.08.90
				Bjarni Arnason