




Loftnet 25mm. p.l.p.
 Sími 50mm. p.l.p.
 Inntak R.H. 50mm. p.l.p.

 Öll rör séu 16mm.
 Ídreginn 3x1,5^a vír.
 Hæð rofa sé 110cm.
 Hæð tengla, SogL dósa sé 20cm.
 Öll mál midast við fullfrágengin gólf og á midja dós.
 Málstraumur rafbúnaðar sé 10A.
 Loftnet:
 Sími - - - - -

Nema annars sé getid.

Vallarbard 16 Hafnarfirði	Mkv. 1:50
Raftögn kjallara.	Dags. 6-84
Hönnun: Kjartan Jarlsson Rafvirki.	Samb. KJ.
	Blad 2 af 4.