



SKÝRINGAR:

- KALT VATN
- HEITT
- KALDAVATNSKRANI
- HEITA
- RENNILOKI
- MED SPINDLI UPPUR JÖRD
- EINSTREYMSLOKI
- VATNSMELIR
- GV GARDVATN

PIPUR SKULU EINANGRADAR MED 20mm GLERULLARHÖLKUM OG VAFÐAR MED PLASTÖK ALLT EFNI, PIPUR OG FITTINGI SKAL VERA GALVANISERAD. KERFI SKAL PRÖFA MED KÖLDU VATNI OG 5 KG/cm² ÞRYSTINGI. BALÐFIX RENNILOKAR SELU VID HVERT TERTI EINSTREYMSLOKI VID ÞVOTTAVELAR. FRAGANGUR INNTAKS OG LOFTPUÐAR SKY FORSKR. VATNSV. R.V.

KERFI ~ 1:50



BREIÐVANGUR 17	MÆLIKVAFDI ~1:50	VERK 7311	TEIKN NR 7
VATNSLÖGN KERFI	Hannað: Teiknað:	Yfirfarð: Samp:	DAGS JULI '73
JÓHANN GUNNAR BERGPÓRSSON VERKFR MVFI KÖLDUKINN 9 - HAFNARFIRÐI - Sími 52895	BREYTT		