


- ATHUGASEMD IR:**
1. GRAFA SKAL NIÐUR A FAST OG FYLLA MEÐ HRAUNFYLLINGU.
 2. FYLLINGUNA SKAL TITRINGSÞJAPPA Í 300 MM LÖGUM.
 3. EINANGRUNARPLAST Þ 50 MM. OG E 20-30 KG/M³ SKAL VERA UNDIR ALLRI PLÖTUNNI OG 500 MM NIÐUR A ÚTVEGG.
 4. STEYPA SKAL VERA S200.

23.08.1990

 Marteinn Guðjónsson

MARTEINN GUÐJÓNSSON TFI OG IS
 ARNARHRAUNI 29 220 HFJ. S. 651045
 LÆKJARBERG 34 HFJ. bl. B1.
 SÖKKLAR
 GERT: OKT. 1990 *Marteinn Guðjónsson*