



SKÝRINGAR: STEYPA ER S-250, SEMENTSINNÍHALD MÍNNST 300 KG/M³ STEYPU, SIGMÁL 5-8 CM. LOFTINNÍHALD 5-6 %.
 ST.ST.JÁRN ER RAFSÖÐIN NET K377. OG KAMBSTÁL KS40.
 ÞEKJULAG STEYPU UTAN Á JÁRNUM ER 30 MM.
 TITRA SKAL ALLA STEYPU.

30 MAY 1988



VERKHÖNNUN
 VERKFRÆÐI OG TEIKNISTOFA
 ÁRMÚLA 21, REYKJAVÍK, SÍMI: 91-39900
 VERK NR 293 TEIKNAD:
 TEIKN NR 102 HANNAD:
 MÆLIKV. 1:100 1:10 SAMPYKKT:
 DAGS. MÁÍ 1988 BREYTT:
 VERKEFNI: VÖRUHÚS, OKS
 HAFNARFIRÐI
 HEITI TEIKN:
 VEGGIR JÁRNBENDING