



SKÝRINGAR: STEYPA ER S-250, SEMENTSÍNNIHALD MÍNNST 300 KG/M³ STEYPU, SIGMÁL 5-8 CM, LOFTÍNNIHALD 5-6 %. ST.ST. JÁRN ER RAFSOÐIN NET K377, OG KAMBSTÁL KS40, ÞEKJULAG STEYPU UTAN Á JÁRNUM ER 30 MM, TITRA SKAL ALLA STEYPU.

30 MAY 1988
30 MAY 1988



VERKHÖNNUN
VERKFRÆÐI OG TEIKNISTOFA
ÁRMÚLA 21, REYKJAVÍK, SÍMI: 91-39900
VERK NR 293 TEIKNAD:
TEIKN. NR 102 HANNAÐ:
MÆLIKV. 1:100 1:10 SAMÞYKKT:
DAGS. MAÍ 1988 BREYTT:
VERKEFNI: VÖRUHÚS, OKS
HAFNARFIRÐI
HEITI TEIKN:
VEGGIR JÁRN BENDING