



LYSING:

| | | | |
|----|-------------|--------------------|-------|
| KS | stoðir | 45 x 145 x 2500 mm | 2 stk |
| KL | lausholt | 35 x 145 x 1108 | 5 |
| TX | trétex | 12 x 1194 x 363 | 1 |
| | | 12 x 1194 x 956 | 1 |
| | | 12 x 51 x 1251 | 2 |
| KR | krossviður | 4 x 50 x 1108 | 5 |
| KU | undirpanell | 22 x 120 x 329 | 6 |
| | | 22 x 120 x 999 | 6 |
| KY | yfirpanell | 22 x 120 x 329 | 5 |
| | | 22 x 120 x 999 | 5 |

stoðir lausholt: 4x100 mm akrúfur 2 og 3 stk pr enda
sbr. teikn. 24 stk pr ein.
trétex grind: snertifletir grindar límbornir
40 mm hefti o/c 100 mm 100-llo stk pr ein.
panell lausholt: 75 mm hefti 2 stk pr borð á lausholt
110 stk pr ein.

(Huggi og gluggafrégangur sbr. gluggateikningu)



| | | |
|--------------------------|---|---------------|
| RVK FEBR 83 | HUSASMIDJAN H. SUBÁVÖGI 3-5, RVK, SÍMI 84599 | GERB. NR. |
| REIKN. TEIKN. SGS YFIRF. | F. FIFUHAMMI KÓPAV. SÍMI 43521 | VERK NR. 7706 |
| MÆLIKV. 1:1 | VALLARÞARÐ 2 | TEIKN NR. |
| | VEGGEINING G2E-12/25 | |