



ADALTAFLA EINLÍNEMYND.

HEIMTAUG R.H. 63A.

KVÍSL FRÁ ADALTAFLU
3x6² - 1" P.

16A GR. 1	TTT 5/8" 3	2.5 ²	ÞURRKARI
16A GR. 2	TTT 5/8" 3	2.5 ²	ÞVOTTAYÉL
10A GR. 3	TTT 5/8" 3	1.5 ²	SVEFNÁLMA
10A GR. 4	TTT 5/8" 3	1.5 ²	SVEFNÁLMA
10A GR. 5	TTT 5/8" 3	1.5 ²	STOFUR
25A GR. 6	TTT 3/4" 3	4.0 ²	ELDAYÉL
10A GR. 7	TTT 5/8" 3	1.5 ²	UPPÞVOTTAYÉL
10A GR. 8	TTT 5/8" 3	1.5 ²	ELDHÚS
N	TTT 5/8" 1	6.0 ²	GRUNNTENGINA BABBUNAPAR.

IBUDARTÖFLUR 1 og 2 HÆÐ

MÁL	1:50	RAFLÖGN II HÆÐ.
DAGS.	12/10 '79	EINLÍNEMYNDIR
BLAÐ	3 af 3	Jón Þ. Guðmundsson dót.