

**BASE PLATE DETAILS**  
**WARD**  
STRUCTURES LMS

Base Type: L  
Base Locations: F12', G12'

SECTION: 152x152x37 UC

200Wide x 25Thick x 200Lg Base Plate.

75 Sq. TAPERED POCKETS  
INSERTS SUPPLIED BY M.CONTRACTOR

BASE TYPE L

2 No. M20 x 375 Lg H.D BOLTS GR:4.6 TOTAL BOLTS = 2  
 100 C/C 's. 2 No SC048 W.PLTS. TOTAL W.PLTS = 2

This drawing is the property of Atlas Ward Structures and must not be copied or reproduced either in whole or in part without written permission.

CLIENT: FORMACO V.B.V. ISTAK SCHOOL	CONT No. 19007	DRN S.R.C. DATE 13.2.99	DRG No. B-12
--	-------------------	----------------------------	-----------------

**BASE PLATE DETAILS**  
**WARD**  
STRUCTURES LMS

Base Type: J  
Base Locations: D4,D5

SECTION: 203x203x71 UC

300Wide x 15Thick x 300Lg Base Plate.

75 Sq. TAPERED POCKETS  
INSERTS SUPPLIED BY M.CONTRACTOR

BASE TYPE J

4 No. M20 x 375 Lg H.D BOLTS GR:4.6 TOTAL BOLTS = 8  
 220 C/C 's. 4 No SC048 W.PLTS. TOTAL W.PLTS = 8

This drawing is the property of Atlas Ward Structures and must not be copied or reproduced either in whole or in part without written permission.

CLIENT: FORMACO V.B.V. ISTAK SCHOOL	CONT No. 19007	DRN S.R.C. DATE 13.2.99	DRG No. B-9
--	-------------------	----------------------------	----------------

**BASE PLATE DETAILS**  
**WARD**  
STRUCTURES LMS

Base Type: K  
Base Locations: F4'

SECTION: 203x203x46 UC

350Wide x 25Thick x 350Lg Base Plate.

75 Sq. TAPERED POCKETS  
INSERTS SUPPLIED BY M.CONTRACTOR

BASE TYPE K

4 No. M20 x 375 Lg H.D BOLTS GR:4.6 TOTAL BOLTS = 4  
 270 C/C 's. 4 No SC048 W.PLTS. TOTAL W.PLTS = 4

This drawing is the property of Atlas Ward Structures and must not be copied or reproduced either in whole or in part without written permission.

CLIENT: FORMACO V.B.V. ISTAK SCHOOL	CONT No. 19007	DRN S.R.C. DATE 13.2.99	DRG No. B-10
--	-------------------	----------------------------	-----------------

**BASE PLATE DETAILS**  
**WARD**  
STRUCTURES LMS

Base Type: WASHER PLATES  
Base Locations: 30 DIA BOLTS

MATERIAL 150x15 FLTx150 LG

220 No REQUIRED AS DRAWN MKD WP1

This drawing is the property of Atlas Ward Structures and must not be copied or reproduced either in whole or in part without written permission.

CLIENT: FORMACO V.B.V. ISTAK SCHOOL	CONT No. 19007	DRN S.R.C. DATE 13.2.99	DRG No. B-11
--	-------------------	----------------------------	-----------------

**BASE PLATE DETAILS**  
**WARD**  
STRUCTURES LMS

Base Type: BOLT QUANTITIES  
Base Locations:

**BOLT QUANTITIES**

M20 GRADE 4.6 x 375 LG H.D. BOLTS	196 No. REQD.
M30 GRADE 8.8 x 450 LG H.D. BOLTS	220 No. REQD.
WASHER PLATES. SC048	196 No. REQD.
WASHER PLATES. WP1	220 No. REQD.

This drawing is the property of Atlas Ward Structures and must not be copied or reproduced either in whole or in part without written permission.

CLIENT: FORMACO V.B.V. ISTAK SCHOOL	CONT No. 19007	DRN S.R.C. DATE 13.2.99	DRG No. B-11A
--	-------------------	----------------------------	------------------