



3 SKÝRINGAR

STEYPA S-250, SEMENTINNIHALD = 300kg/M  
 STEYPUHULA Í ÖTVEGGJUM = 30mm  
 STEYPUHULA Í PLÖTU = 20mm  
 BENDISTÁL Ks410

BENDING VEGGJA  
 ÖTVEGGJIR EINFÖLD GRIND Í ÖTBRÓN  
 LÁRÉTT K12 c/c 150#  
 LÖBRET K12 c/c 180#  
 MILLIVEGGIR EINFÖLD GRIND  
 K12 c/c 180#  
 MILLIVEGGIR MILLI IBOÐA  
 K12 c/c 150#

Br.	Dags.	Eðli breytinga	Sign

ESKIVELLIR 7  
 HAFNARFIRÐI

BENDING VEGGJA 4 HÆÐAR  
 BENDING PLÖTU YFIR 4 HÆÐ

MKV. 1:50 1:20

DAGS. MAÍ. 2005 04 JUNÍ 2005

VERK NR. 2422 Byggingafulltrúinn í Hafnarfirði  
 F.h. Sigurbjartur Halldórsson

TEIKN. NR. 1-06A

HANNAÐ SIG. ÞORLEIFSS. KT. 241148-3009

TEIKNAD G.H.

YFIRFARID

TÆKNISJÓNUSTA SIGURDAR ÞORLEIFSSONAR ehf  
 STRANDGÖTU 11 220 HAFNARFIRÐI  
 Sími 555-4255 FAX 565-2875  
 E-mail taeknihjonusta@islandia.is  
 kt: 440693-2539