



SKÝRINGAR
 STEYPA S=250, SEMENTINNIHALD = 300kg/m
 STEYPUHULA Í GTFEGGJUM = 30mm
 STEYPUHULA Í PLÖTU = 20mm
 BENDISTAL Ks410

BENDING VEGGJA
 GTFEGGJUR TVÖFOLD GRIND K10 c/c 200#
 Milliveggr tvöföld grind
 K10 c/c 200#
 Milliveggr einföld grind í miðjan vegg
 K10 c/c 250#
 EDA BENDINET 181

Br.	Dags.	Eðli breytinga	Sign
DAGGARVELLIR 4B HAFNARFIRÐI			
BENDING VEGGJA 2 HÆÐAR BENDING PLÖTU YFIR 2 HÆÐ Sambýkt þann 13 OKT. 2004			
MKV. 1:50 1:20			
DAGS. FEB. 2004			
VERK NR. 2332			
TEIKN. NR. 1-05			
HANNAD SIG. ÞORLEIFSS. KT. 241148-3009			
TEIKNAD G.H.			
VEIÐARÍÐ			
TEIKNIÞJÓNUSTA SIGURDAR ÞORLEIFSSONAR ehf STRANDGÖTU 11 220 HAFNARFIRÐI SÍMI 555-4255 FAX 565-2875 E-mail teeknihjonusta@islandia.is KT: 440693-2539			