


GRUNNMYND 1 HÆÐAR 1:50

OFN NR.	STÆÐUR BLÓMVELLIR 10	HITAÞÖRF WÖTT	MESTA LENGD	MESTA HÆÐ	TENGING
101	BÍLGEYMSLA	3,080	2200	600	
102	ÞVOTTUR	620	700	600	
103	VS	230	500	600	
104	HERB	1,190	1500	600	
105	GANGUR	930	900	600	
106	ELDHÚS	910	800	600	
107	STOFA	1,570	2100	210	VK+C
108	STOFA	2,350	3200	210	VK+C
109	ANDD	710	700	600	
110	GEYMSLA	450	800	600	
201	HJÓN	2,130	1600	600	
202	HANDKILÖFN				
203	GEYMSLA	560	600	600	
204	FJÖLDSK	1,800	1400	600	
205	HERB	2,130	2000	600	
206	FJÖLDSK	720	800	600	
207	GANGUR	720	800	600	
	SAMTALS	20,100			

Br.	Dags.	Eðli breytinga	Sign

## BLÓMVELLIR 10 HAFNARFIRÐI

HITA-VATNS OG FRÁRENSLILAGNIR  
1 HÆÐAR



Sambýkkt þann

MKV. 1:50

2. FEB. 2004

DAGS. MAÍ. 2003

VERK NR. 2310

Byggingafræðingur í Hafnarfirði  
E.h. Sigurbjartur Halldórsson

TEIKN. NR. 2-02

HANNAÐ SIG. ÞORLEIFSS. KT. 241148-3009

TÆKNAD G.H.

YFIRFIRIÐ

TÆKNIFÉLAGIÐ SIGURDAR ÞORLEIFSSONAR ehf

STRANDGÖTU 11 220 HAFNARFIRÐI

SÍMI 555-4255 FAX 565-2875

E-mail taeknihjonusta@islandia.is



*Handwritten signature*