

Öfn nr.	Afköst [W / 7t 30°C]	Hæð [mm]	Lengd [mm]	Tenging		Gerð	Stýring
				a	c		
101	1.124	300	2000	A - D		Panel 22	Framrásaríokí
102	1.124	300	2000	A - D		Panel 22	Framrásaríokí
103	1.348	300	2400	C - B		Panel 22	Framrásaríokí
104	1.124	300	2000	C - B		Panel 22	Framrásaríokí
105	592	300	1000	A - B		Panel 22	Framrásaríokí
106	592	300	1000	C - D		Panel 22	Framrásaríokí
107	1.124	300	2000	C - D		Panel 22	Framrásaríokí
108	1.348	300	2400	A - D		Panel 22	Framrásaríokí
109	1.124	300	2000	C - B		Panel 22	Framrásaríokí
110	1.124	300	2000	A - B		Panel 22	Framrásaríokí
111	1.090	140	2400	A - B		Runtal VK+C	Framrásaríokí
112	819	500	1400	A - B		Panel 11	Framrásaríokí
113	819	500	1400	A - B		Panel 11	Framrásaríokí
114	872	500	2200	C - D		Panel 11	Framrásaríokí
115	1.124	300	2000	A - B		Panel 22	Framrásaríokí
116	1.348	300	2400	C - B		Panel 22	Framrásaríokí
117	1.124	300	2000	A - D		Panel 22	Framrásaríokí
118	1.124	300	2000	A - D		Panel 22	Framrásaríokí
119	490	300	800	C - D		Panel 22	Framrásaríokí
120	1.090	140	2400	C - B		Runtal VK+C	Framrásaríokí
121	1.124	300	2000	C - B		Panel 22	Framrásaríokí
122	1.124	300	2000	C - B		Panel 22	Framrásaríokí
123	1.348	300	2400	A - B		Panel 22	Framrásaríokí
124	1.124	300	2000	C - B		Panel 22	Framrásaríokí
Samtals	24.848	W 66					

Öfn nr.	Afköst [W / 7t 30°C]	Hæð [mm]	Lengd [mm]	Tenging		Gerð	Stýring
				a	c		
125	819	500	1400	A - B		Panel 11	Framrásaríokí
126	872	500	2200	C - D		Panel 11	Framrásaríokí
127	1.808	2000	830	A - B		Runtal VKM-2	Framrásaríokí
128	1.124	300	2000	C - B		Panel 22	Framrásaríokí
129	1.124	300	2000	A - B		Panel 22	Framrásaríokí
130	1.899	2000	830	A - B		Runtal VKM-2	Framrásaríokí
131	756	500	1200	A - B		Panel 21	Framrásaríokí
132	1.701	500	2000	A - B		Panel 22	Framrásaríokí
133	1.701	500	2000	A - B		Panel 22	Framrásaríokí
134	490	500	900	A - B		Panel 11	Framrásaríokí
135	819	500	1400	C - B		Panel 11	Framrásaríokí
Samtals	12.882	W 66					

Öfn nr.	Afköst [W / 7t 30°C]	Hæð [mm]	Lengd [mm]	Tenging		Gerð	Stýring
				a	c		
136	1.124	300	2000	A - D		Panel 22	Framrásaríokí
137	1.124	300	2000	A - D		Panel 22	Framrásaríokí
138	1.348	300	2400	C - B		Panel 22	Framrásaríokí
139	1.124	300	2000	A - D		Panel 22	Framrásaríokí
140	1.080	140	2400	C - B		Runtal VK+C	Framrásaríokí
141	874	300	1200	A - B		Panel 22	Framrásaríokí
142	1.124	300	2000	A - B		Panel 22	Framrásaríokí
143	1.124	300	2000	A - B		Panel 22	Framrásaríokí
144	1.348	300	2400	A - D		Panel 22	Framrásaríokí
145	1.124	300	2000	A - D		Panel 22	Framrásaríokí
146	872	500	2200	A - B		Panel 11	Framrásaríokí
147	819	500	1400	C - D		Panel 11	Framrásaríokí
148	819	500	1400	C - B		Panel 11	Framrásaríokí
149	1.124	300	2000	A - B		Panel 22	Framrásaríokí
150	1.124	300	2000	A - B		Panel 22	Framrásaríokí
151	1.348	300	2400	A - B		Panel 22	Framrásaríokí
152	1.124	300	2000	C - B		Panel 22	Framrásaríokí
153	592	300	1000	A - D		Panel 22	Framrásaríokí
154	592	300	1000	C - D		Panel 22	Framrásaríokí
155	1.124	300	2000	A - B		Panel 22	Framrásaríokí
156	1.348	300	2400	A - B		Panel 22	Framrásaríokí
157	1.124	300	2000	C - B		Panel 22	Framrásaríokí
158	1.124	300	2000	C - B		Panel 22	Framrásaríokí
159	1.080	140	2400	C - D		Runtal VK+C	Framrásaríokí
Samtals	26.072	W 66					

Slófu nr.	Afköst [W]	Blí m/llí lagna [mm]	Lengd [m]	Harbergjahlid [°C]	Vatnsmagn [l/mín]	Stýring
1	945	250	58	22	1,89	T1
2	1723	250	108	22	3,08	T2
3	1902	250	117	22	3,40	T3
4	1720	250	108	22	3,05	T3
5	1515	250	93	22	2,71	T3
6	1520	250	96	22	2,75	T2
7	805	250	37	22	1,08	T2
8	1723	250	108	22	3,08	T4
Samtals	11.853		721		20,88	

T = hitastillir á vegg, stýrir samsvarendi mótörökum

Slófu nr.	Afköst [W]	Blí m/llí lagna [mm]	Lengd [m]	Harbergjahlid [°C]	Vatnsmagn [l/mín]	Stýring
9	945	250	58	22	1,89	T5
10	1725	250	108	22	3,08	T6
11	1910	250	121	22	3,59	T7
12	1820	250	112	22	3,28	T7
13	1485	250	82	22	2,88	T7
14	1820	250	112	22	3,28	T8
Samtals	9.778		604		17,48	

T = hitastillir á vegg, stýrir samsvarendi mótörökum

Mötend: **KISK**
 22. APRIL 2004
 0 T APR. 2004

Byggingarfulltrúinn í Hafnarfirði
 E. Sigurðsson

NR	DAGS	BREYTING	SAMÞ
FERILL VERKFRÆÐISTOFAN FERILL EHF. F.R.V. HÖRKIN 1 - 108 REYKJAVÍK Sími: 575-1600 FAX: 575-1601 NETFANG: ferill@ferill.is			
LEIKSKÓLI - ÁSBRAUT 4 OFNA OG GÓLFHITASKRÁR			
MKV	TEIKN KÁÁ	DAGS ÚTG 24.02.04	TEIKN NÚMER 955-3-12
ÁRITUN HÖNNUÐAR	KT	SAMÞYKKT	
HÖNNUBUR BREYTINGAR	DAGS BREYTINGAR	BREYTING NR	