



SNID I MALBIK OG HELLUR SJÁ TEIKN. 00812-P15

HELSTU KENNISTÆRDIR :
 STÆRD UPPHITADS FLATAR 290 m²
 HEILDARLENGD HITALAGNA 3160 m
 REIKNAD HITASTIG VATNS AÐ SNJÓBR. 40 °C
 REIKNAD HITASTIG VATNS FRÁ SNJÓBR. 20 °C
 AFKÖST SNJÓBRÆDSLU Á m² 125 W/m²
 HEILDARAFKÖST SNJÓBRÆDSLU 98750 W
 VATNSMAGN FRÁ HITAKERFI HÖSS 1,3 l/s
 REIKNAD VIÐBÓTARMAGN FRÁ HITAVEITU 0,590 l/s

| | | | |
|---|--|---|------------------|
| SKÚTAHRAUN 6, HAFNARFIRDI | | Samþykkt þann 27 NOV. 2003 Byggingafulltrúi / Hafnarfirdi Eh. Sigurbjartur Halldórsson | |
| SNJÓBRÆDSLULAGNIR GÁMASVÆÐI | | Breyting: | |
| V S B VERKFRÆÐISTOFA | | Samþ.: Björn Guðarsson | Kl.: 180550-4889 |
| BEJARHRAUN 20 • 220 HAFNARFJÓRÐUR Sími 895-8600 • FAX 895-9010 Netfang: vsb@vab.is, ic710798-2899 | | Mikr: 1:100 | Telnað: LA |
| | | Daga: 16.03.01 | Nr: 00812-P17 |

Handwritten signature/initials