



2. hæð

OFNASKRÁ $\Delta t = 40^\circ\text{C}$

OFN NR.	AFL W	Staður	HÉÐ mm	LENGD mm	Gerð	Hitastýringartakar	
						Frænnisli	
201	1694	Eldhús	500	1200	Panel		
202	760	Forstofa	600	600	Panel		
203	2250	Stofa	400	2200	Panel		
204	1438	Stofa	400	1400	Panel		
205	1079	Herbergi	600	1000	Panel		
206	1253	Herbergi	600	1000	Panel		
207	673	Bað	600	400	Panel		
208	1079	Hjón	600	1000	Panel		
209	290	Þvottur	600	400	Panel		
210	1079	Gangur	600	1000	Panel		
201a	1694	Eldhús	500	1200	Panel		
202a	760	Forstofa	600	600	Panel		
203a	2250	Stofa	400	2200	Panel		
204a	1438	Stofa	400	1400	Panel		
205a	1079	Herbergi	600	1000	Panel		
206a	1253	Herbergi	600	1000	Panel		
207a	673	Bað	600	400	Panel		
208a	1079	Hjón	600	1000	Panel		
209a	290	Þvottur	600	400	Panel		
210a	1079	Gangur	600	1000	Panel		

Samtals: 23.188 W

Áður en ofnápöntun er staðfest skal yfirfara ofnasterðir á byggingastað.

Samþykkt þann
 07 OKT. 2003
 Byggingafulltrúinn í Hálfmátti
 E.h. Sigurbjartur Halldórsson

Ragnar G.

Angi S. Pálsson

Breytingar			DRASTARÁS 2.	Mkv. 1:50
Nr.	Dags.	Nafn		
			Tæknipjónusta Ragnars G Gunnarssonar ehf. Smíðjuvegi 11 s. 544 5350 fax: 544 5351	Nr. 23
			Grunnmynd 2. hæð hiti, vatn, frænnisli og loftþræsing	Dags. 13.8. 2003
				kt.: 110947-2839