



1. hæð

Grunnm. 1.h.

OFNASKRÁ  $\Delta t = 40^\circ\text{C}$

OFN NR.	AFL W	Staður	HÉÐ mm	LENGD mm	Gerð	Hitastýrðirlekar
						Framrensli
101	1694	Eldhús	500	1200	Panel	
102	760	Forstofa	600	600	Panel	
103	2250	Stofa	400	2200	Panel	
104	1438	Stofa	400	1400	Panel	
105	1079	Herbergi	600	1000	Panel	
106	1253	Herbergi	600	1000	Panel	
107	673	Bað	600	400	Panel	
108	1079	Hjón	600	1000	Panel	
109	290	Þvottur	600	400	Panel	
110	1079	Gangur	600	1000	Panel	
101a	1694	Eldhús	500	1200	Panel	
102a	760	Forstofa	600	600	Panel	
103a	2250	Stofa	400	2200	Panel	
104a	1438	Stofa	400	1400	Panel	
105a	1079	Herbergi	600	1000	Panel	
106a	1253	Herbergi	600	1000	Panel	
107a	673	Bað	600	400	Panel	
108a	1079	Hjón	600	1000	Panel	
109a	290	Þvottur	600	400	Panel	
110a	1079	Gangur	600	1000	Panel	

Samtals: 23.188 W

Áður en ofnápöntun er staðfest skal yfirfara ofnasterðir á byggingastað.

Samþykkt þann  
07 OKT. 2003  
Byggingafulltrúinn í Hafnarfirði  
F.h. Sigurbjartur Halldórsson

*Rann*

*Andri G. Pálsson*

Breytingar			DRASTARÁS 2.
Nr.	Dags.	Nafn	
			Tækniþjónusta Ragnars G Gunnarssonar ehf. Smíðjuvegi 11 s: 544 5350 fax: 544 5351
			Grunnmynd 1. hæð hiti, vatn, frærensli og loftræsing
			Mkv. 1:50 Nr. 22 Dags. 13.8. 2003 kt.: 110947-2839