


GRUNNMYND 1 HÆÐAR 1:50

OFN NR.	STAÐUR	HITAÞÖRF KCAL/H	MESTA LENGD	MESTA HÆÐ
101	STOFA	910	900	400
102	STOFA	2,140	2300	400
103	ANDD	700	800	600
104	ÞVOTTUR	480	600	600
105	BÍLGEYMSLA	2,110	1800	600
106	GEYMSLA	800	600	600
107	HERB	950	1700	600
108	BAD	430	600	600
109	HERB	1,070	1700	600
201	HJÓN	1,110	1300	600
202	HERB	1,120	1300	600
203	SJÓNVARPSH	610	600	600
204	SJÓNVARPSH	1,220	1100	600
205	GEYMSLA	420	600	600
206	BAD	430	600	600
SAMTALS=		15,490		

Br.	Dags.	Eðli breytinga	Sign

KJÓAHRAUN 12 HAFNARFIRÐI

HITA VATNS OG FRÆRENNISLAGNIR
1 HÆÐAR



23 JAN. 2003

MKV. 1:50

DAGS. JAN. 2003

VERK NR. 2001

TEIKN. NR. 2-02

MANNAÐ SIG. ÞORLEIFSS. KT. 241148-3009

TEIKNIAÐ G.H.

YFIRFARID Jón Leimundsson

TÆKNIJÓNUSTA SIGURÐAR ÞORLEIFSSONAR ehf
STRANDGÖTU 11 220 HAFNARFIRÐI
SÍMI 555-4255 FAX 565-2875
E-mail taeknihjonusta@islandia.is