



OFNASKRÁ $\Delta T 40^\circ$

NR.	HITATAP KCAL/T	OFN RUNTAL	TENGI
1	1550	VK 63/3/1000	A B
2	570	C 28/1100	A D
3	930	C 21/2/1100	A D
4	850	V 63/1800	A D
5	725	V 63/1700	A D
6	520	V 35/2/1100	A D
7	1345	C 28/3/700	C B
8	1330	V 63/1600	A D
9	590	V 63/1200	A B
10	250	H 35/2/600	A B
11	1110	V 63/2/1400	A B
12	1780	V 35/2/3500	C B
13	3980	V 56/2/5300	C B 15
14	1215	V 77/2/1200	A B
15	1155	V 42/3/1500	A D
16	750	V 56/1700	A D
17	720	V 56/1700	A D

SKÝRINGAR:

REIKNAD ER MED RUNTAL OFNUM SJA OFNASKRÁ
STILLIHNE OG LOFTSKRÚFA A ÖLLUM OFNUM
DANFOSS RAVL LOKAR A ÖLLUM OFNUM NEMA
NR. 2.6.7.10.11.13.14

ÞAR SEU DANFOSS FJVR. PÍPUR VENJULEGAR SVARTAR
SKAL MALA MED ASFALTMALNINGU OG EINANGRA
MED MINNST 20 mm GLERULLARHÖLKUM OG
VEFJA MED PLASTDÚK.

VEGGJAEINANGRUN A.M.K. 2 1/2" PLAST.

ÞAKEINANGRUN A.M.K. 4"

TVÖFALT GLER I GLUGGUM.

PÍPUR LIGGI I EINANGRUN ÚTVEGGJA EDA
I GÖLFRAUFUM.

— TAKNAR RAS (HEITAR PÍPUR)

- - - - - BAKRAS (KALDAR PÍPUR)



HEIÐVANGUR 11	MÆLIKVARDI ~1:50	VERK 7322	TEIKN NR 8
HITALÖGN KERFI	Hannað: AS. Teiknað: AS.	Yfirfarir: Samp: SB	DAGS JAN '74
JÓHANN GUNNAR BERGÞÓRSSON VERKFR MVFI KÖLDUKINN 9 - HAFNARFIRDI - SÍMI 52895	BREYTT		