



OFNASKRÁ

NR OFNS	HERBERGI	VALDIR OFNAR, DELTA t=40				TENING A-B-C-D	TEGUND	ltr/klst	P	STILL.	ENDANLEG STILLING
		GERD RUNTAL	AFKÖST Wött	LENGD mm	ÞYKKT mm						
1.01	Anddyri	VK+C-28	3069	3000	140	AB					
1.02	Anddyri	VK+C-28	2762	2700	140	CD					
1.03	Kennslustofa	VK+C-28	3159	3000	140	AB					
1.04	Kennslustofa	VK+C-28	2527	2400	140	AB					
1.05	Kennslustofa	VK+C-28	2455	2400	140	AB					
1.06	Kennslustofa	VK+C-28	2455	2400	140	AB					
1.07	Kennslustofa	VKM2-56	1526	1200	95	AB					
1.08	Sérkennsla	VKL2-42	1613	1800	95	CD					
1.09	Sérkennsla	VKL2-42	1971	2200	95	AB					
1.10	Sérkennsla	VKL2-42	2330	2600	95	CD					
1.11	Höprými	VKL+V-56	1568	1800	80	CD					
1.12	Höprými	VKL+V-56	1568	1800	80	AB					
1.13	Aðst. kvöldsk	VK-56	1330	1800	45	CD					
1.14	Kennslustofa	VKL+V56	1306	1500	80	AB					
1.15	Kennslustofa	VKL+V56	1306	1500	80	AB					
1.16	Gangavörður	V-56	609	1400	30	CD					
2.01	Kennslustofa	VK+C2-28	3045	1800	205	AB					
2.02	Kennslustofa	VK+C2-28	3045	1800	205	AB					
2.03	Kennslustofa	VK+C2-28	2538	1500	205	CD					
2.04	Kennslustofa	VK+C2-28	3722	2200	205	AB					
2.05	Kennslustofa	VK+C2-28	3722	2200	205	CD					
2.06	Kennslustofa	VK+C2-28	3722	2200	205	AB					
2.07	Kennslustofa	VK+C2-28	3722	2200	205	AB					
2.08	Kennslustofa	VKM2-56	1272	1200	95	AB					
2.09	Föt	VKL3-42	2336	1800	140	AB					
2.10	Kennslustofa	VKL3-42	2855	2200	140	AB					
2.11	Kennslustofa	VKL3-42	3375	2600	140	CD					
SAMTALS			64908								

SETBERGSSKÓLI 3.-ÁFANGI  
HLÍÐARBERGI  
HAFNARFIRÐI

ÞRIFA- OG HITAKERFI  
GRUNNMYND 2. HÆÐAR

**VERKFRÆÐISTOFA**  
**STEFÁNS & BJÖRNS**  
BEIARHRAUNI 20 • 220 HAFNARFJÖRDUR  
SÍMI 565-1340 • FAX 565-1341  
Netfang: vb@centrum.is, kt: 01886-1419

Hanna: BG Telkno: BG Yfirskj.  
Mök: 1:50 Samþykkt: *Björn Jónsson*  
Dag: 08.02.1996 Nr. 9551-L04-A

*Ösif H*