



SKÝRINGAR

TIMBUR Í BURDARVIRKI SKAL VERA K18 SAMKVÆMT IST/DS 413
SKRUFUR BOLTAR OG TENGISTYKKI SKULU VERA RYÐVARIN MED SINKHÜÐ
K 40/40, TÁKNAR KAMBSAUM TD. BMF, (lengd=40mm þvermál=4mm)
ALAG: EIGINÞUNGI LOFTS 0.45 Kn/m²
NOTALAG 1.0 Kn/m²

VERKFRÆDISTOFA SUÐURLANDS EHF. AUSTURVEGI 3-5, 800 SELFOSS S: 482 3900 Fax: 482 2711		BLAD: 01
HÖLSHRAUN 1B, HAFNARFIRDI, APÓTEK EHF		KVARDI 1:50 1:10
MILLIGÖLF ÚR TIMBRI		REIKN: E.I. TEIKN: E.I.
DAGS: 23.02'97		DAGS: 23.02'97
NR:	DAGS	BREYTING
AF	SAMP: <i>Erlingur Ingvarsson</i>	
NR: 97019		