



- Mælagrind.
1. Renniloki
 2. Sía
 3. Hæmil
 4. Vatnemælir
 5. Einstöfnuloki
 6. Hitastýrnur ventill, t.d. Danfoss AVTB/RAVV
 7. Hita og þrýstímælir
 8. Þrýstímælir
 9. Þrýstijafnari, t.d. Danfoss AVD-DA
 10. Slaufuloki, t.d. Danfoss AVD-RA
 11. Öryggislöki
- Ⓐ Inntak, kalt vatn #32mm
 - Ⓑ Inntak, heit vatn #32mm
 - Ⓒ Kalt neysluvatn #25mm
 - Ⓓ Heit neysluvatn #25mm
 - Ⓔ Frammrás hitaveitu #25mm
 - Ⓕ Bakrás hitaveitu #25mm
 - Ⓖ Frammrás enjóbæðslu #25mm
 - Ⓗ Bakrás enjóbæðslu #25mm

20 FEB 1992

Breytingar			Klapparholt 7, Hafnarfirði	
Nr.	Dags.	Nafn		
1.	14.02.92	Asmundur	Asmundur Asmundsson verkfræðingur Hamraborg 14A, Kóp. sími 44473	SJ T SJ S
				M 1:50
			Hita og neysluvatnslagnir	Nr. 91.04-2.04
			Rúmmynd <i>Asmundur</i>	Dags. 10.91
				204