



GRUNNMYND 1. HÆÐAR 1:50

OFN NR.	STADUR KRIUÁS 3	HITAÞÖRF KCAL/H	MESTA LENGD	MESTA HÆÐ
101	HERB	780	1400	600
102	ELDHÚS	1,140	1400	400
103	STOFA	2,180	3600	400
104	HJÓN	880	1800	600
105	HJÓN	880	1800	600
106	STOFA	2,180	3000	400
107	ELDHÚS	1,140	1400	400
108	HERB	780	1400	600
109	HJÓL/VAGNAR	550	800	600
201	HERB	1,140	1800	600
202	HERB	980	1400	600
203	ELDHÚS	1,300	1400	400
204	STOFA	2,330	3600	400
205	HJÓN	1,020	1800	600
206	HJÓN	1,020	1800	600
207	STOFA	2,330	3600	400
208	ELDHÚS	1,300	1400	400
209	HERB	980	1400	600
210	HERB	1,140	1800	600
SAMTALS		24,050		

Br.	Dags.	Eðli breytinga	Sign
<b>KRIUÁS 3</b> <b>HAFNARFIRÐI</b> HITA-FRÁRENNSLIS OG LOFRÆSTILAGNIR 1. HÆÐAR			
MKV. 1:50		 14. MARS 2001	
DAGS. FEB. 2001		 Sigurbjartur Halldórsson	
VERK NR. 2049			
TEIKN. NR. 2-06			
HANNAD sig 241148-3009			
TEIKNAD G.H.			
YFIRFARIÐ			
TÆKNIPJÓNUSTA SIGURDÓTTA ÞORLEIFSSONAR ehf. STRANDGÖTU 11 220 HAFNARFIRÐI Sími 666-4666 FAX 666-6976 E-mail teknipj@teknipj.com			

24.1/3/01  
GHB