



OFNASKRÁ-PANEOFNAR				
Ofn nr.	gerð hæð	lengd	afköst wött	tenging
101	21 / 500	1000	804	AB
102	21 / 500	1000	804	AB
103	21 / 500	1000	804	AB
104	11 / 500	1000	506	AB
105	21 / 500	1000	804	AB
106	22 / 300	2000	1289	AÐ
107	21 / 300	1000	586	AB
108	11 / 600	600	371	CD
109	21 / 500	1000	804	AB
		Alls	6772 W	

SKÝRINGAR.

Öll ofntengi séu 10 mm.

A hvern ofn komi loftskrúfa og stillití

A hvern ofn komi DANFOSS Ravl framrennislóki

Lögn tengist við eldri mælagrind.

———— Framrennslí hitaveitu

———— Bakrennslí hitaveitu

----- Heitt neysluvatn

----- Kalt neysluvatn

Öll mál í mm

LINDARBERG II

JÓHANNES BENEDIKTSSON

SKÁLABERG VIÐBYGGING

M 1:50

okt'89

Hitalagnir pípuviðdir

staðsetning tækja

Johannes Benediktsson

