


MARK	LENGTH	THK	DEPTH
6ZP108	7580	3.0 mm	216 mm
6ZP111	7401	3.0 mm	216 mm
6ZP295	8228	1.5 mm	216 mm
7ZP304	7542	3.0 mm	216 mm
7ZP323	7569	3.0 mm	216 mm
ZP109	7580	1.5 mm	216 mm
ZP110	7161	3.0 mm	216 mm
ZP112	6982	1.9 mm	216 mm
ZP113	7401	1.5 mm	216 mm
ZP114	7401	1.9 mm	216 mm
ZP252	8228	2.1 mm	216 mm
ZP253	8228	1.9 mm	216 mm
ZP256	7590	1.9 mm	216 mm
ZP293	8228	3.0 mm	216 mm
ZP329	7618	1.5 mm	216 mm
ZP334	7590	1.5 mm	216 mm
ZP347	7618	1.9 mm	216 mm
ZP371	7170	3.0 mm	216 mm
ZP378	7199	1.9 mm	216 mm

All Dimensions are millimeters [mm.] -Unless Noted



▲ SSR FIXED CLIPS

- ③ PSM00107
- ② 305
- ① 314

* Denotes A325 Secondary to Frame Connection

On: filesrv Projky: 38890 Bldg: 2 Plane: 6,7

This Drawing is Sealed only as to the Components furnished by VP Buildings

- UNLESS NOTED, USE 1/2" DIAMETER A-307 BOLTS FOR PURLIN LAP, PURLIN TO FRAME, FLANGE BRACE TO FRAME, AND FLANGE BRACE TO PURLIN CONNECTIONS. SEE JOB DETAILS FOR BOLT LENGTHS.
- WIND, FLANGE, AND PURLIN BRACING ARE AN INTEGRAL PART OF THE ROOF STRUCTURAL SYSTEM AND SHOULD BE PROPERLY INSTALLED PRIOR TO ERECTION OF WALL AND ROOF SHEETS. REMOVAL OR ALTERATION OF ROOF BRACING WITHOUT PRIOR AUTHORIZATION IS PROHIBITED.
- WHEN SAG ANGLE SLOTS IN ADJACENT PURLINS DO NOT ALIGN OR ARE OMITTED, FIELD-BEND A SAG ANGLE TAB AND ATTACH TO PURLIN WITH A SELF-DRILLING STRUCTURAL FASTENER.
- SAG ANGLES ARE NOT REQUIRED IN BAYS THAT ARE 16' OR LESS.

Building Code:	86MBMA
Live Ld (W/Trib Red):	102.5 kgsm
Coll. Ld (gravity):	24.4 kgsm
Coll. Ld (uplift):	0.0 kgsm
Wind Speed:	170.6 kmph
Wind Exp. Cat.:	C
Ground Snow:	146.5 kgsm
Roof Snow:	102.5 kgsm
Snow Exp. Cat.:	3
Seismic Zone:	3
Building Use Cat.:	1
Auxiliary Loads	NONE


This Drawing, including the information hereon, remains the property of VP Buildings. It is provided for Erecting the Building described in the applicable Purchase Order and shall not be modified, reproduced or used for any other purpose without prior written Approval of VP Buildings. The General Contractor and/or Erector is solely responsible for accurate, good Quality Workmanship in erecting this Building in conformance with this Drawing. Details referenced in this Drawing, all applicable VP Buildings Erection Details and all industry Standards pertaining to proper erection, including the correct use of temporary Bracing.

REV	DATE	BY	DESC.	BUILDER
				Varco-Pruden Exports
				CUSTOMER: Sindri
				LOCATION: Iceland,
				PROJECT: Sindri Workshop
				BUILDING: workshop 2

QUOTE # ME99012531-001

VP BUILDINGS
VARCO-PRUDEN

JOB #	--1
DATE	08/16/99
TIME	02:39
DRAW/CHECK	DHG
PAGE	13



Verkfæðistofa Norðurlands ehf.
Höfðabót 4 600 Akureyri, kt. 560175-0869
Eiríkur Jónsson byggingaverkfr.
kt. 051045-4679

VERKFRÆÐISTOFANORÐURLANDS ehf.