

Ofn nr.	Heiti rýmis	Varmþ. Wött	Ofnaval	Tegund	Hæð mm	Lengd mm	Þykkt mm	Afköst Wött	Rennslí /klst.	A B	C D	Stýring ofnloka	á vegg steypu	á vegg létan	á gólf	Athugasemdir
1.01	Fataherbergi	2.845	Runtal	V+C2	140	1.500	185	1.445	31	A - B	Fra+Bak			X	Tengist gólfhital.	
1.02	Fataherbergi		Runtal	V+C2	140	1.500	185	1.445	31	C - D	Fra+Bak			X	Tengist gólfhital.	
1.03	Salerni	630	Runtal	CP	210	1.000	95	725	16	A - B	Framrás		X		Þvingað streymi (ÞS)	
1.04	Hvild	1.190	Runtal	VKM2	210	2.000	95	1.270	27	A - B	Framrás		X		Þvingað streymi	
1.05	Leikstofa	2.780	Runtal	CP	210	1.300	95	940	20	A - B	Framrás		X		Þvingað streymi	
1.06	Leikstofa		Runtal	VKL+V	560	2.200	80	1.915	41	C - D	Framrás		X		Þvingað streymi	
1.07	Eldhús	2.250	Runtal	VKM	350	2.700	45	1.350	29	A - B	Framrás		X		Þvingað streymi	
1.08	Eldhús		Runtal	(H) VK	420	1.800	45	1.065	23	A - B	Framrás		X		Upp á ránd, ÞS	
1.09	Kaffistofa starfsmanna	1.840	Runtal	VK+C	210	2.200	140	1.840	40	C - D	Framrás		X		Þvingað streymi	
1.10	Fataherbergi og gangur	2.605	Runtal	VK+C	210	900	140	755	16	A - B	Fra+Bak			X	Teng. gólfhital. ÞS	
1.11	Fataherbergi og gangur		Runtal	VK+C	210	1.900	140	1.590	34	C - D	Fra+Bak			X	Teng. gólfhital. ÞS	
1.12	Leikstofa	1.885	Runtal	VK+C2	210	1.400	205	1.940	42	A - B	Framrás			X	Þvingað streymi	
1.13	Salerni	725	Vor-yl	1	600	1.450	59	730	16	A - D	Framrás		X			
1.14	Leikstofa	720	Vor-yl	A	600	1.130	59	750	16	A - B	Framrás		X			
1.15	Hvild	945	Vor-yl	1	600	970	59	485	10	A - B	Framrás		X			
1.16	Hvild		Vor-yl	1	600	1.130	59	565	12	A - B	Framrás		X			
1.17	Tengibygging	3.895	Runtal	C2	210	2.100	160	2.160	46	A - B	Bakrás			X	Teng. gólfhital. ÞS	
1.18	Tengibygging		Runtal	VKL	560	2.100	45	1.255	27	C - D	Bakrás	X			Teng. gólfhital. ÞS	
1.19	Kastali	4.345	Vor-yl	C	600	1.450	103	1.825	39	A - B	Framrás	X			Tengist gólfhital.	
1.20	Kastali		Vor-yl	C	600	1.450	103	1.825	39	A - B	Framrás	X			Tengist gólfhital.	
1.21	Viðtalsherbergi	700	Vor-yl	B	600	810	103	820	18	A - B	Framrás	X				
1.22	Sérkennari	605	Vor-yl	2	600	810	103	650	14	A - B	Framrás	X				
1.23	Skólastjóri	1.290	Vor-yl	B	600	1.450	103	1.475	32	A - D	Framrás	X				
1.24	Vinnuherbergi	1.060	Vor-yl	2	600	1.450	103	1.170	25	C - B	Framrás	X				
1.25	Fataklefi	5.615	Runtal	C3	210	1.500	240	2.315	50	A - B	Fra+Bak			X	Teng. gólfhital. ÞS	
1.26	Fataklefi		Runtal	C3	210	1.500	240	2.315	50	C - D	Fra+Bak			X	Teng. gólfhital. ÞS	
1.27	Fataklefi/ræsting		Handklæðaofn		800	500	80	300	6	E - F	Framrás		X			
1.28	Fataklefi/purkherbergi		Vor-yl	A	280	810	59	305	7	A - D	Framrás		X			
1.29	Salerni	600	Handklæðaofn		1.800	500	80	720	15	E - F	Framrás	X				
1.30	Salerni	640	Handklæðaofn		1.800	500	80	720	15	E - F	Framrás		X			
Samtals		37.165						36.665					8	14	8	

Ofn nr.	Heiti rýmis	Varmþ. Wött	Ofnaval	Tegund	Hæð mm	Lengd mm	Þykkt mm	Afköst Wött	Rennslí /klst.	A B	C D	Stýring ofnloka	á vegg steypu	á vegg létan	á gólf	Athugasemdir
1.31	Leikstofa	1.890	Vor-yl	C	600	1.450	103	1.825	39	A - D	Framrás	X				
1.32	Leikstofa	1.805	Vor-yl	C	600	1.450	103	1.825	39	C - B	Framrás	X				
1.33	Leikstofa	1.310	Vor-yl	B	600	1.450	103	1.475	32	C - B	Framrás	X				
1.34	Leikstofa	1.725	Vor-yl	B	400	2.430	103	1.820	39	C - B	Framrás	X				
1.35	Hvild	1.015	Vor-yl	B	600	970	103	980	21	C - D	Framrás	X				
1.36	Listastofa	1.840	Vor-yl	A	600	2.910	59	1.925	41	C - B	Framrás		X			
1.37	Hvild	1.175	Vor-yl	A	600	1.940	59	1.280	28	C - B	Framrás	X				
Samtals		10.760						11.130					6	1		

Nr. Lysing & þreyingu. Dags.

LEIKSKÓLINN NORÐURBERG
NORÐURVANGI 13, HAFNARFIRÐI

PIPUKERFI
ELDRI BYGGING OG NYBYGGING
OFNATAFLA

Byggingaútlit frá Hamnarfjarðar Afgreitt þann 07 MARS 2000

Kvart: ENGINN
Móttöl: mBG/PSK
Tæknab: HBG
Virknab: P.07
Verk nr: 241
Skjal nr: 241-Norðurberg-HB-Reyðvín.dwg

LAGNATÆKNI
HÖNNUNAR- OG RÁÐGJAFARSTOFA
HAMRABORG 12, 200 KÖPAVOGUR
Sími: 564 5252 Fax: 564 5251
Netfang: it@lagnatak.is

Samp: *Jóni S. Jónsson*
Kennitala: 300346-34109