

Ofnastærðir mældast við delta tm = 40°C Allir ofnstútar eru 10 mm. Allir ofnar eru frá Ofnasmíðjunni

Ofn nr.	Heiti rýmis	Varmabörf Wött	Ofnaival	Tegund	Hæð mm	Lengd mm	Þykkt mm	Afköst Wött	A B C D	Staðsetning ofnlóka	Athugasemdir	Valdir ofnar
.01	Sérdeild	10.760	Toppofn	DK	520	2.000	97	2.379	A-B	Framrás		
.02	Sérdeild		Toppofn	DK	520	3.000	97	3.569	A-D	Framrás		
.03	Sérdeild		Toppofn	DK	520	3.000	97	3.569	C-D	Framrás		
.04	Sérdeild		Toppofn	DK	520	800	97	952	A-B	Framrás		
.05	Sérdeild		Toppofn	ER	520	800	18	340	A-B	Framrás		
.06	Tæklistofa	4.811	Gólfhitalögn	WisboPEX	20	114	xx	2.444	XX	Framrás	Gólfhitalögn	
.07	Tæklistofa		Gólfhitalögn	WisboPEX	20	115	xx	2.444	XX	Framrás	Gólfhitalögn	
.08	Geymsla f. tæklistofu	891	Toppofn	C	520	900	97	888	A-D	Framrás	Skípt upp í tvö herbergi	
.08A	Geymsla	690	Toppofn	C	520	700	97	691	C-D	Framrás	Skípt upp í tvö herbergi	
.09	Salerni fatlaóra	396	Toppofn	ER	520	1.000	18	425	A-B	Framrás		
.10	Munir v/hannyrðastofu	750	Toppofn	ER	520	1.800	18	767	C-B	Framrás		
.11	Efni v/hannyrðastofu	978	Toppofn	EK	520	1.500	45	994	A-D	Framrás		
.12	Hannyrðastofa	7.324	Toppofn	DK	520	3.400	97	4.045	C-B	Framrás		
.13	Hannyrðastofa		Toppofn	C	520	3.400	97	3.355	A-B	Framrás		
.14	Hannyrðastofa		Toppofn	ER	520	500	18	212	C-D	Framrás		
.15	Hjálpar kennsla	3.826	Toppofn	DK	520	3.400	97	4.045	A-D	Framrás		
.16	Gangur v/sérdeild	662	Toppofn	EK	520	1.000	45	662	C-D	Framrás		
.17	Míðrymi og lyfta	5.903	Svissyl	323	210	2.600	134	2.444	C-D	Framrás		
.18	Míðrymi og lyfta		Svissyl	323	210	3.800	134	3.573	C-D	Framrás		
.19	Alm. Kennslustofa	4.712	Toppofn	DR	520	3.400	97	2.516	A-D	Framrás		
.20	Alm. Kennslustofa		Toppofn	DR	520	3.400	97	2.516	C-B	Framrás		
.21	Alm. Kennslustofa	4.712	Toppofn	DR	520	3.400	97	2.516	A-D	Framrás		
.22	Alm. Kennslustofa		Toppofn	DR	520	3.400	97	2.516	C-B	Framrás		
.23	Alm. Kennslustofa	4.712	Toppofn	DR	520	3.400	97	2.516	A-D	Framrás		
.24	Alm. Kennslustofa		Toppofn	DR	520	3.400	97	2.516	C-B	Framrás		
.25	Alm. Kennslustofa	4.853	Toppofn	DR	520	3.400	97	2.516	A-D	Framrás		
.26	Alm. Kennslustofa		Toppofn	DR	520	3.400	97	2.516	C-B	Framrás		
.27	Bækur	1.359	Toppofn	C	520	1.500	97	1.480	C-B	Framrás		
.28	Ræsting	535	Handklæðafn	1060-33H	1.191	600	30	552	E-F	Framrás		
.29	Ræstingastólur	643	Toppofn	C	520	700	97	690	C-B	Framrás		
.30	Þvottarhúsi	908	Handklæðafn	1075-50H	1.803	750	30	1.021	E-F	Framrás		
.31	Hópharberg	1.419	Toppofn	EK	520	2.300	45	1.524	A-D	Framrás		
.32	Silgahúsi	2.267	Svissyl	324	280	1.400	134	1.527	C-D	Bakrás	Slá einnig ofn nr. 76	
.33	Gangur og setkrókur	5.179	Svissyl	433	210	2.000	196	2.662	C-D	Framrás		
.34	Gangur og setkrókur		Svissyl	433	210	2.000	196	2.662	A-B	Framrás		
.35	Ferstofo	2.619	Svissyl	324	280	2.600	134	2.837	C-B	Bakrás		
.36	Anddyr	2.430	Svissyl	434	280	900	196	1.404	C-D	Framrás	Lenqd slaufu 52 m	
.37	Anddyr		Svissyl	434	280	900	196	1.404	A-B	Framrás	Lenqd slaufu 52 m	
.38	Smíðastofa	11.434	Toppofn	DK	520	3.400	97	4.045	A-D	Framrás		
.39	Smíðastofa		Toppofn	DK	520	3.400	97	4.045	C-B	Framrás		
.40	Vélar		Toppofn	DK	320	2.100	97	1.752	C-D	Framrás		
.41	Munageymsla		Toppofn	C	320	1.800	97	1.184	C-D	Framrás		
.42	Smíðastofa		Toppofn	DK	520	700	97	832	C-D	Framrás		
.43	Lökkun		Handklæðafn	1050-50H	1.803	500	30	697	A-B	Framrás		
.44	Kennari		Toppofn	EK	520	500	45	331	A-B	Framrás		

Ofnastærðir mældast við delta tm = 40°C Allir ofnstútar eru 10 mm. Allir ofnar eru frá Ofnasmíðjunni

Ofn nr.	Heiti rýmis	Varmabörf Wött	Ofnaival	Tegund	Hæð mm	Lengd mm	Þykkt mm	Afköst Wött	A B C D	Staðsetning ofnlóka	Athugasemdir	Valdir ofnar
.45	Hópharberg	2.230	Toppofn	EK	520	3.400	45	2.253	C-D	Framrás		
.46	Alm. Kennslustofa	5.146	Toppofn	C	520	3.000	97	2.960	A-D	Framrás		
.47	Alm. Kennslustofa		Toppofn	DR	520	3.000	97	2.219	C-B	Framrás		
.48	Setkrókur og gangur	6.395	Svissyl	433	210	2.200	196	2.929	A-B	Framrás		
.49	Setkrókur og gangur		Svissyl	433	210	2.200	196	2.929	C-D	Framrás		
.50	Setkrókur og gangur		Toppofn	ER	720	1.100	18	633	A-B	Framrás		
.51	Alm. Kennslustofa	4.787	Toppofn	DR	520	3.400	97	2.516	A-D	Framrás		
.52	Alm. Kennslustofa		Toppofn	DR	520	3.400	97	2.516	C-B	Framrás		
.53	Ahöld	1.362	Toppofn	C	520	1.500	97	1.480	A-B	Framrás		
.54	Ræsting	619	Handklæðafn	1050-50H	1.803	500	30	697	E-F	Framrás		
.55	Opló ryml	6.638	Toppofn	DR	520	2.100	97	1.554	A-D	Framrás		
.56	Opló ryml		Toppofn	DR	520	2.100	97	1.554	C-B	Framrás		
.57	Opló ryml		Toppofn	DR	520	2.100	97	1.554	A-D	Framrás		
.58	Opló ryml		Toppofn	C	520	2.100	97	2.072	C-B	Framrás		
.59	Kennari	905	Toppofn	C	520	1.000	95	987	A-B	Framrás		
.60	Búr	552	Toppofn	ER	520	1.400	18	596	A-B	Framrás		
.61	Hústiðrnarstofa	8.804	Toppofn	DK	520	3.400	97	4.045	C-B	Framrás		
.62	Hústiðrnarstofa		Toppofn	DK	520	3.400	97	4.045	C-B	Framrás		
.63	Hústiðrnarstofa		Toppofn	C	520	900	97	888	C-B	Framrás		
.64	Alm. Kennslustofa	4.793	Toppofn	DR	520	3.400	97	2.516	A-D	Framrás		
.65	Alm. Kennslustofa		Toppofn	DR	520	3.400	97	2.516	C-B	Framrás		
.66	Alm. Kennslustofa	4.793	Toppofn	DR	520	3.400	97	2.516	A-D	Framrás		
.67	Alm. Kennslustofa		Toppofn	DR	520	3.400	97	2.516	C-B	Framrás		
.68	Alm. Kennslustofa	4.793	Toppofn	DR	520	3.400	97	2.516	A-D	Framrás		
.69	Alm. Kennslustofa		Toppofn	DR	520	3.400	97	2.516	C-B	Framrás		
.70	Alm. Kennslustofa	5.350	Toppofn	C	520	3.400	97	3.355	A-D	Framrás		
.71	Alm. Kennslustofa		Toppofn	DR	520	3.400	97	2.516	C-B	Framrás		
.72	Ahöld	1.407	Toppofn	C	520	1.500	97	1.480	C-D	Framrás		
.73	Geymsla	1.868	Toppofn	DK	520	1.600	97	1.903	C-B	Framrás		
.74	Ræsting	718	Handklæðafn	1060-50H	1.803	600	30	826	E-F	Framrás		
.75	Hópharberg	1.584	Toppofn	EK	520	2.400	45	1.590	A-B	Framrás		
.76	Silgahúsi	2.627	Toppofn	DK	720	2.300	97	3.465	A-D	Framrás	Slá einnig ofn nr. 32	
.77	Gangur og setkrókur	6.817	Svissyl	433	210	2.200	196	2.929	C-D	Framrás		
.78	Gangur og setkrókur		Svissyl	433	210	2.200	196	2.929	A-B	Framrás		
.79	Gangur og setkrókur		Toppofn	EK	720	1.100	45	974	A-B	Framrás		

Samtals varmaþörf 1. Afanga, wött 156.961

Samtals afköst ofna 164.065 wött

10. des. 1997

VINNUTEIKNING

22. des. 1997

		HÖNNUNAR OG RÁÐGJAFARSTOFA HAMRABORG 12 200 KÓPAVOGUR Sími: 564 5252 Fax: 564 5251 Netfang: lagnotak@islandia.is		EINSETNING ÖLDUTUNSSKÓLA í afanga- og viðbyggingu PÍPUKERFI HITA- OG NEYSLUVATNSKERFI OFNATAFLA		Kenni: ENGINN Hönnun: HBG/FSK Tæknib: HBG Verki: 181 Skjal nr.: 181HELD	
A 12.97 OFNI 08 SKIPT UPP Í TVO OFNA 08 OG 08A HBG		Daga: Þreyning		Daga: Des. 1997 Blað nr.: P. 14A		Kennitala: 300346-3409	