



SNID Í RAMMA (LÍNA 8)

Ø stærd	styrkur	torque Ma (m.Kp.)	
	8.8	10.9	12.9
M12	9.46	13.20	15.95
M16	23.10	31.90	39.05
M20	45.10	63.80	75.90
M22	60.50	85.80	102.30
M24	78.10	110.00	132.00
M27	115.50	165.00	198.00
M30	159.50	220.00	264.00



VEKTOR - hönnun og ráðgjöf - Nýbýlavegi 6, 200 Kópavogi.		Sigurður Hafsteinsson byggingafræðingur M. 000628-7749 sími: 554-8660 fax: 554-8998	
Tölu nr. _____ Samþykkt _____ Dags. _____		Óseyrarbraut 40 Skipaskáli Sníð í ramma Hárrað _____ Tel.nr. _____	
Dagaþing _____ Ágúst 1999 S850		Vark nr. _____ Málkvarði _____ Tel.nr. _____ 1:100 S850/2SP	