



- SKÝRINGAR:**
1. SKEMATSK KERFMYND AF LOFTHITAKERFLUM, SJÁ TEKNINGU NR. G0258A/M15/1/030.
 2. SKEMATSK KERFMYND AF OFNHITAKERFLUM, SJÁ TEKNINGU NR. G0258A/M15/1/036.
 3. GRUNNMÝND PÍPULAGNA FYRIR EFRRI HÆÐ, SJÁ TEKNINGU NR. G0258A/M15/1/034.
 4. [2800] HÆÐ FRA NESTA GÖLF I MEÐA PÍPU. (NESTA GÖLF KÖTI =0,00)
 5. ALLAR ÖMENDAR ENDALAGNIR I ÖFNA ERU $\phi 10$ MM.
 6. BOKSTAFURINN "T" VÐ PÍPU MERKIR FRAMRÁS, BOKSTAFURINN "R" VÐ PÍPU MERKIR BAKRÁS.
 7. ALLAR HITALÖGN ER ÖR SVÖRTUM STÁLDRÖRUM OG ERU ÞAR EINAÞRAGÐAR MEÐ GLEFLLARHÖLUM. ALLAR NÁNARI SKÝRINGAR ERU I VERNINGSLUM.

C-15	MÍÐAR BRYTINGAR OG LAZZINGAR Á PÍPULÖG, TENGING STAFKERS OG HYRFAFN Á STÖMUM	22/10/98
B-15	TENGING PÍPULAGNA AF HÆÐA OG BATT NÁN MEÐU FORSJA EHF. ÞROTTI LÖGNA AF HITAKERFLUM I TÖRKLARLA OG FL.	02/03/98
TENDER ISSUE		
B	PIPE, VALVES TO RADIATORS REDUCED TO 10mm PRESSURE FOR TENDER #P/M/1	15/11/97
A	ISSUED FOR TENDER #P/M/1	15/10/97
Rev	Description	Date

Drawing Created by OH on 19/08/97
 CAD by DVF/sp Plotted



Tanahire House, Shackleford Road, Epsstead, Surrey GU8 5LB UK
 Telephone: +44 (0)252 703993 Fax: +44 (0)252 703684

Client: **DELTA HF ICELAND**
 Project: **NY LYFJAVERKSMÍÐJA**
 Drawing Title: **HITAKERFLI: GRUNNMÝND NEDRI HÆÐAR**

FORSJÁ
 VERKFRÆÐISTOFA FRV
 SKOGLANDSVEGUR 3, REYKJANÍK
 SM: 503 690 OG 552 4710, FAX: 562 4300
 NETTÖL: forsj@berntinn.is

CAD File: M083C-is Scale: 1:75
 Drawing No.: **G0258A/M15/1/083C-is**
 THIS IS A COMPUTER PRODUCED DRAWING
 DO NOT AMEND BY HAND