



HURDIR Á VEGG MILLI SKRIFSTOFUBYGGINGAR OG STEYPUKÁLA ERU STAÐHURDIR MEÐ PLEXIGLERI, 0.3x0.4M. ATLUNIN ER AD SKIPTA ÚT PLEXIGLERINU OG SETJA Í STAÐINN A.M.K. TVÖFALT 6MM ÞRÁÐGLER.

VEGGUR MILLI SKRIFSTOFUBYGGINGAR OG STEYPUKÁLA ER BYGGÐUR ÚR JÄRNBEITNUM SIENSTEYPTUM ENINGUM, 200MM ÞYKKUM Á VEGGNUM ERU GLUGGAR, 4 STK. Á 2.HÆÐ OG 2 STK. Á 3.HÆÐ HVER GLUGGI UM SIG ER 1.0x1.3 M. TVÖFALT GLER ER Í GLUGGUNUM EN ATLUNIN ER AD SETJA Í STAÐINN A.M.K. TVÖFALT 6MM ÞRÁÐGLER.

SKÝRINGAR
 RÖMNINGARLEIÐ
 MERKI ÖTUNGULEIÐ

ENGN NEYÐARLÝSING ER NÓI HÖSINU. ATLUNIN ER AD BETA ÖR BESSU OG MERKJA ÖTUNGULEIÐ I SAMRÉMI VÖ TEKNINGAR.

REV. NO.	DATE	REVISION	BY	APP.	REV. NO.	DATE	REVISION	BY	APP.	NOTES	REFERENCE DRAWING	DRAWING NUMBER	SCALE	FORMAT	REVISION
3	29.11.1997	EINS OG BYGGT ER, "AS BUILD"		UH											
2	10.2.1997	BUNINGSHERBERGI ENDURBETT OG BADADSTADA STÆKKUD		UH											
1	3.9.1996	STÆKKUN SVALASVÆDIS ÚR 10M Í 17M		UH											
0															

This drawing is our property and given for personal use only. It may not be copied or made available to others without our permission. The receiver is responsible for any misuse.

ICELANDIC ALUMINIUM COMPANY LTD.

ALUSUISSE ALESA

ALUSUISSE ENGINEERING LTD. ZÜRICH SWITZERLAND

VERKFRÆDISTOFAN ÖNN SF. TÆKNITHJONUSTAN SF.

STÆKKUN STEYPUKÁLA - BRUNAHÖNNUN GRUNNMYND

GRUNNMYND VINNSLUGÓLF'S

SCALE 1:250

79000-34423

193.623

3