


GRUNNMYND JARÐHÆÐAR 1:50

OFN NR.	STAÐUR	HITAÞÖRF KCAL/H	RESTA LENGD	RESTA HÆÐ
101	BAÐ	390	600	600
102	HERB	830	1400	600
103	FJÖLSK	1,320	1600	600
104	HERB	780	1400	600
201	GEYMSLA	410	600	600
202	ÞVOTTUR	350	600	600
203	BÍLGEYMSLA	2,200	1900	600
204	ANDD	550	800	600
205	VS	330	500	600
206	ELDHÚS	1,420	1100	500
207	STOFA	1,590	1400	400
208	STOFA	1,410	1600	400
209	STOFA	850	1000	400
210	HJÓN	1,400	1400	600
SAMTALS=		13,830		

Br.	Dags.	Eðli breytinga	Sign
<b>ÞRASTARÁS 32</b> <b>HAFNARFIRÐI</b>			
HITA-VATNS OG FRÁRENNISLAGNA JARÐHÆÐAR			
MKV. 1:50		 07. DES. 2001	
DAGS. NÓV. 2001		Byggingafulltrúinn í Hafnarfirði F.h. Sigurbjartur Halldórsson	
VERK NR. 2102			
TEIKN. NR. 2-02			
HANNAÐ SIG. ÞORLEIFSS. KT. 241148-3009			
TEIKNAD G.H.			
YFIRFARIÐ			
<b>TÆKNIPJÓNUSTA</b> SIGURDAR ÞORLEIFSSONAR ehf STRANDGÖTU 11 220 HAFNARFIRÐI Sími 555-4255 FAX 565-2875 E-mail taeknihjonusta@islandia.is			

AKL 5/12/01  
Lsp