



TENGIMYND HITAVEITU

OFNASKRÁ $\Delta T = 40^\circ C$

NR.	HITATAP KCAL/T.	MESTA LENGD	MESTA HÆÐ	TENGI	OFN-
101	2040	400cm	70cm		
102	840	180-	50-		
103	2055	360-	18-		
104	330	50-	50-		
105	550	70-	70-		
106	840	170-	18-		
107	1410	260-	58-		
108	210	70-	58-		
109	210	70-	58-		
110	1060	160-	65-		
201A	1155	80-	50-		
201B		80-	50-		
202	580	160-	58-		
203	715	160-	58-		
204	725	70-	70-		
205	580	160-	58-		
206	1410	160-	58-		
207	490	150-	50-		

31. júlí 1980

OFNAR VELJIST Í SAMRÁÐI VIÐ ARKITEKT.

SKÝRINGAR SJÁ TEKN. NR. 20.

HÚS C III

TÚNHVAMMUR 2	MÆLIKVARDI /	VERK 8001	TEIKN NR 2.7
TENGIMYND HITAVEITU	Hannað: <i>[Signature]</i> Teiknað: <i>[Signature]</i>	Yfirfarið: <i>[Signature]</i> Samþ: <i>[Signature]</i>	DAGS JÚNÍ '80
JÓHANN GUNNAR BERGÞÓRSSON VERKFR. MYFI STRANDGÖTU 11 - HAFNARFIRÐI - Sími 53315	BREYTT		