



STEINSTEYPA
 STEYPA ER C25/30 MED A.M.K. 300 Kg SEMENT l m³.

LOFTINNHÁLD STEYPU : 6-8 %
 V/S-TALA (UMHVERFISFLOKKUR 2b) : < 0,55
 SIGMÁL STEYPU (S2) : 50 - 90 mm
 MESTA STEINASTÆRD : 32 mm
 TITRA SKAL ALLA STEYPU.

STEYPUHULA Á JÄRNUM
 GILDIN EIGA VID UM VENJULEGAR ADSTÆÐUR, EF ANNAD ER EKKI SÝNT Á TEIKNINGUM. ÞAR SEM TÆRINGARHÆTTA ER MIKIL GILDA ADRAR REGLUR UM STEYPUHULU JÄRNA.

	PLÖTUR	VEGGIR	BITAR	SÚLUR
INNANHÜSS	15	20	20	20
UTANHÜSS	25	25	25	25
SÖKKLAR	35	35	35	35
STEYPT AD JÖRD	50	50	50	50

UM BITA OG SÚLUR GILDIR EINNIG: C1 ≥ 1.5xd

STEYPUSTYRKARSTÁL
 STÁLGÆDI: K - KAMBSTÁL f_{yk} = 500 Mpa
 BEYGING STÁLS d = ALLIR SVERLEIKAR

SKEYTING BENDISTÁLS ER SAMKVÆMT EFTIRFARANDI: D = 5 x d

PVERMÁL STÁLS, d	10	12	16
SKEYTIENGD l mm	500	600	800

LÁRÉTT JÄRN SEM KOMA Í HORN EDA PVERVEGG SKAL BEYGJA SKEYTIENGD FYRIR HORN.

BENDING Í SÖKKULVEGGI
 2 K12 EFST OG NEDST
 K10 c/c 250 LÓDRÉTT
 K10 c/c 300 LÁRÉTT.

MÁL ERU l mm NEMA ANNARS SÉ GETIÐ.

WA
 VERKFRÆÐISTOFA ÁRÞORGAR ehf
 AUSTURVEGI 69 800 SELFOSS
 Sími 480 4900 FAX 482 3851
 www.vefharborg.is vefharborg@vefharborg.is

SGHUS
 AUSTURVEGI 69 800 SELFOSS
 Sími 482 3850 FAX 482 3851
 NETFANG sghus@sghus.is
 VEFFANG www.sghus.is

HAFRAVELLIR 5 Hafnarfirði

BURDARVIRKI: MKV.
 SNID Í SÖKKUL MKV. 1:20
 SKÝRINGAR OG GRUNDUN MKV. 1:50

HANNAÐ: T.ELLERT-TÓMASSON TEIKNÁÐ: LAURA APARISI
 VERKNÖMUR: 6073 SKRÁRNAMN: 6073-bv.dwg
 DAGSETNING: 28.08.2006 SAMÞYKKT: *[Signature]* TEIKNING NÖMUR: 202-A

BREYTING DAGS: 09.11.2006
 HVERJU BREYTT: SÖKKUL HÆÐ ÚR 1200 Í 800
 BREYTT AF: T.ELLERT