


SKÝRINGAR SJÁ TEIKNINGU P-2

OFNASKRÁ	Ofn nr.	Afl W	Hæð mm	Lengd mm	Tegund	Staðs. stúta	Ofnlokar	
Bílgeymsla	1	3.400	500	2800	22	A-D	Framrás	
Geymsla	2	630	500	700	21	C-B	Framrás	
Herbergi	3	1.030	600	1400	11	C-B	Framrás	
Dnddyri	4	540	500	600	21	C-B	Framrás	
Stofa / borðstofa	5	643	300	800	22	A-D	Framrás	
Stofa / borðstofa	6	1.600	300	2000	22	A-D	Framrás	
Stofa / borðstofa	7	1.600	300	2000	22	A-D	Framrás	
Stofa / borðstofa	8	1.470	600	2000	11	A-D	Framrás	
WC	9	500	500	1100	Handkl.	----	Bakrás	
Skáli	10	880	600	1200	11	A-D	Framrás	
Hjón	11	1.240	600	1400	21	A-D	Framrás	
Herbergi	12	1.030	600	1400	11	A-D	Framrás	
Þvottur	13	740	600	1000	11	A-D	Framrás	
		15.303						

Dýsingadultrúll Hafnarfjarðar  
 Afgreitt þann  
 30. JAN. 2006

Daga	Brayfingar	Nr.	Notn
30.01.2006	Rámmynd breytt	1	FG
 <b>meter Verkfæðistofa ehf</b> Síðumúli 1 108 Reykjavík Sími: 5678922, Fax: 8940059 meter@meter.is, www.meter.is			
FLÉTTUVELLIR 25, 221 HAFNARFJÖRDUR			
GRUNNLAGNIR, AFSTÖÐUMYND OG SKÝRINGAR			
TOLVUSKRA	MANNAD	TEKNAÐ	YFIRFARÐ
183-221-FLÉTTUVELLIR 25	DGP	DGP	FO
SAMÞYKKI	TEKNING NR.	MKV.	BLAD NR.
Frjálsk. Guðsson	183-P4	1:50/1:500	P-04
FRITTUN SAMRÆMINGARFRÉTTINGAR	DAGS.	VERK NR.	
Frjálsk. Guðsson	30.01.2006	183	