



STEINSTEYPA

STEYPA ER C25/30 MED A.M.K. 300 Kg SEMENT í m<sup>3</sup>.

LOFTINNIHALD STEYPU : 6-8 %

V/S-TALA (UMHVERFISFLOKKUR 2b) : < 0.55

SIGMÁL STEYPU (S2) : 50 - 90 mm

MESTA STEINASTÆRD : 32 mm

TITRA SKAL ALLA STEYPU.

STEYPUHULA Á JÄRNUM

GILDIN EIGA VIÐ UM VENUJLEGAR AÐSTÆÐUR, EF ANNAD ER EKKI SÝNT Á TEIKNINGUM. ÞAR SEM TÆRINGARHÆTTA ER MIKIL GILDA ADRAR REGLUR UM STEYPUHULU JÄRNA.

	PLÖTUR	VEGGIR	BITAR	SÚLUR
INNANHÜSS	15	20	20	20
UTANHÜSS	25	25	25	25
SÖKKLAR	35	35	35	35
STEYPT AD JÖRD	50	50	50	50

UM BITA OG SÚLUR GILDIR EINNIG: C1 ≥ 1.5x d

STEYPUSTYRKARSTÁL

STÁLGÆDI: K - KAMBSTÁL fyk = 500 Mpa

BEYGING STÁLS d= ALLIR SVERLEIKAR

SKEYTING BENDISTÁLS ER SAMKVÆMT EFTIRFARANDI: D = 5 x d

ÞVERMÁL STÁLS, d í mm	10	12	16
SKEYTILENGD í mm	500	600	800

LÁRÉTT JÄRN SEM KOMA Í HORN EDA ÞVERVEGG SKAL BEYGJA SKEYTILENGD FYRIR HORN.

BENDING Í SÖKKULVEGGI 2 K12 EFST OG NEDST K10 c/c 250 LÓDRÉTT K10 c/c 300 LÁRÉTT.

MÁL ERU í mm NEMA ANNARS SÉ GETID.

Byggingafulltrúi Hafnarfjarðar Afgreitt þann 27 JUN 2006

VERKFRÆÐISTOFA ÁRBORGAR ehf  
AUSTURVEGI 69 800 SELFOSSI  
SÍM 480 4900 FAX 482 3851  
www.verkarborg.is verkarborg@verkarborg.is

AUSTURVEGI 69 800 SELFOSSI  
SÍM 482 3850 FAX 482 3851  
NETFANG sghus@sghus.is  
VEFFANG www.sghus.is

**GLITVELLIR 39**

BURDARVIRKI: MKV.

SNID Í SÖKKUL: MKV. 1:20

SKÝRINGAR OG GRUNDUN: MKV. 1:50

HANNAÐ: T. ELLERT TÓMASSON TEIKNAD: LAURA APARISI

VERKNÚMÉR: 6038 SKRÁRVAFN: 6038-bv.dwg

DAGSETNING: 12.04.2006 SAMÞYKKT: *[Signature]* TEIKNING NÚMÉR: 202

201170-3979