



ARITUN SAMRÆMINGARÞÓKNUNAR  
 Kr. 110457-2789

SKYRINGAR:  
 SVÆDI PAR SEM KÚLUM OG JÄRNUM Í EFRI BRÚN SLEPPT  
 SVÆDI PAR SEM KÚLUM ER SLEPPT

STEYPA Í KÚLUPLÖTUR:  
 BROTTÓLSFLOKKUR: C25/30  
 SEMENTSMAGN: MINNST 320 kg/m³  
 VÁTNSSEMENTSTALA: < 0,50  
 HÁMARKSSTEINASTÆRD: 25 mm  
 LOFTTINNHALD: 5 - 6%  
 FIJRL-STUÐULL LOFTS: < 0,25mm  
 LÁGMARKSHULA: 25 mm

Byggingafræðingur  
 Alvarstið bann  
 22.11.2005

TILVÍSANIR:  
 BENDING KÚLUPLATNA. . . . . SJÁ BL. NR. B(15)\_155

A	02.01.19	FIERSKA GATA	HE	GG
BR.	DAGS	BREYTING	REKNI	TEKNI
<b>NORÐURBAKKI 15</b>				
BURÐARVIRKI				
SÉRMYNDIR AF KÚLUPLÖTUM				
PLATA YFIR 1. HÆD				
MRV.:	1:50			
DAGS:	01.12.2005			
HANNAÐ/TEKNI:	HEGG			
VERKNI:	05104			
YRFARÐ:		ÞÓ		
SAMÞYKKT:		<i>Julius</i>		
KENNITALA:		130657-4438		
TEKNI NR:		B(15)_151		
BR:		A		

