



NOTE : STITCH PORTAL BRACE
TO MEZZANINE FRAME COLUMN WITH
M20 x 50 BOLTS 8.8 DIN 933.

USE BACKING PLATE (CL 19) AND M20 x 60 BOLTS
TO UPPER AND LOWER CONNECTIONS.

USE 2mm PACKING PLATE (CL 6 / CL 7) .

STITCH C8 TO MEZZANINE FRAME COLUMN

USE BACKING PLATE (CL 19) AND M20 x 60 BOLTS
TO UPPER AND LOWER CONNECTIONS.

USE 2mm PACKING PLATE (CL 14 / CL 15) .

YOU CAN USE SHIM
PLATES FOR BASE:

2 mm 479292
3 mm 479293
5 mm 479294

NOTE : ALL BOLTS HAVE A NUT (DIN 934)
AND 1 WASHER (DIN 125).

VEKTOR
Byggingarumrör Hafnarfjörður
Hönnu og ráðgjöf ehf.
Kl. 10894-429

10 MAY 2006
VPS

NO.	REVISION	DATE	SIGNATURE
 H-4400 NYÍREGYHÁZA DERKOVITS ÚT 119. TEL.: +36 42 501 310 FAX.: +36 42 312 029	ORDER NAME	DRAWING TITLE	SCALE
	STEINHELLA 5 HAFNARFJORDUR	GL - C & GL - E	1:150 1:150
	ORDER No.	DRAWING No.	DATE
	2961.1	107	27.04.2005
		REV.	MADE BY
			L.H.
			CHECKED BY