



STITCH C9 TO MEZZANINE FRAME COLUMN  
WITH M20 x 60 BOLTS 8.8 DIN 933.  
USE BACKING PLATE (CL 19) TO THE CONNECTIONS.  
ALL BOLTS HAVE A NUT (DIN 934)  
AND 1 WASHER (DIN 125).

YOU CAN USE SHIM  
PLATES FOR BASE:  
2 mm 479292  
3 mm 479293  
5 mm 479294

**VEKTOR**  
Hönnun og ráðgjöf ehf.  
Byggingafræðingur  
Afgreitt þann  
10 MAY 2006  
VPS.

NO.	REVISION	DRAWING TITLE	SCALE	DATE	SIGNATURE
		STEINHELLA 5 HAFNARFJORDUR	1:150 1:150	27.04.2005	L.H. CHECKED BY
			ORDER No. 2961.1	DRAWING No. <b>108</b>	REV.

**Lindab**  
Building Systems  
H-4400 NYÍREGYHÁZA  
DERKOVITS ÚT 119.  
TEL.: +36 42 501 310  
FAX: +36 42 312 029